

1 030505

API NUMBER 15- 151-21,680 - 00-00 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SW, SEC. 18, T 29 S, R 15 *W/X*

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625 & 7105

Lease Name Thompson Well # 1

Operator: VAC Petroleum Co./Spines Exploration, Inc. County Pratt 162.50

Name & Address 333 North Rock Road, No. 105

Well Total Depth 5000 Simpson feet

Wichita, KS 67206

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 434

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 1:00 pm Day: 30 Month: August Year: 1985

Plugging proposal received from Wayne Boughner

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 950'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 470' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:30 pm Day: 30 Month: August Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 970' with 50 sx cement, 2nd plug at 470' with 50
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1985

9-6-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Anhydrite

INVOICED

(if additional description is necessary, use BACK of this form.)

(operator/driver) observe this plugging.

DATE SEP 10 1985

Signed Steve Durrant (TECHNICIAN)

INV. NO. 9918