

To: 1 052164 9-2 API NUMBER 15- 151-21,825 -00-00
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App. SW NW SE SW SEC. 18, T 29 S, R 15
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License / _____
Operator: Kansas Corporation Commission
Name: _____
Address: 130 S. Market, Rm. 2078
Wichita, KS 67202

973 feet from S section line
3933 feet from E section line
Lease Name Thompson Wright Well / I
County Pratt
Well Total Depth 4920 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 2 Month: 9 Year: 19 97

Plugging proposal received from Richard Lacey

(company name) KCC (phone) 316-338-1610

Core: 5 1/2" at 4910', PBSD 4835', Perfs NA

1st plug sand back to above Mississippi perfs and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 2 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 5 sx cement on top of sand through bailer on 8/28/97,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and ISIP 0 psi (not on vacuum).

Rec'd
9-9-97

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)