

1 040540

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,290 - 00-00

SW SW SW, SEC. 18, T. 26 S, R. 13 W/EX

330 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Petrowsky Well # 1

Operator: Pintail Petroleum, Inc.

County Pratt 146.25

Name & Address 412 E. Douglas

Well Total Depth 4500 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 500

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 31 Month: 5 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4499' est., PBSD 4012', Perfs at 4308-12, 3967-70'

1st plug sand back to 50' above perfs and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 31 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3890' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 250 psi and shut in 0 psi.

RECEIVED STATE CORPORATION COMMISSION

6-7-91 JUN 7 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1826' of 4 1/2" casing. (If additional description is necessary, use BACK of this form. Wichita, Kansas)

INVOICED observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE: 6-18-91

INV. NO. 32168