

1,090109

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Docket #D-24,689

SE SW NW, SEC. 21, T 26 S, R 13 W/E

2970 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30705

Operator: B-Y Operating, Inc.

Name:

Address 251 N. Water, Suite 10

Wichita, KS 67202

Lease Name Dodson Well # A-1

County Pratt

151.77

Well Total Depth 4670 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 465

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Dual Completion

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12:35 p.m. Day: 14 Month: 8 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4610' w/225 sx cement, PBSD 4590', Perfs at 4374-78, Open hole 4610-70'

1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:15 p.m. Day: 14 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 100 sx cement.

Maximum pressure 250 psi and shut in 50 psi.

RECEIVED STATE CORPORATION COMMISSION 8-19-91 AUG 19 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2135' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(I could not observe this plugging.)

DATE 8-28-91

INV. NO. 32860

Signed [Signature] (TECHNICIAN)