

To: 1 090110
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-14 116
API NUMBER 15-151-21,545-00-00

SE NW SW, SEC. 21, T 26 S, R 13 W/E
1650 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30705

Lease Name Frisbee Well # C-1

Operator: B-Y Operating, Inc.
Name & Address 251 N. Water, Suite 10
Wichita, KS 67202

County Pratt 148.52

Well Total Depth 4570 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 14 Month: 8 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4569' w/225 sx cement, PBTD 4424', Perfs at 3826-32, 3961-68, 4436-42'

1st plug sand back to 3770' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:04 a.m. Day: 14 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3770' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 200 psi and shut in 25 psi.

RECEIVED
STATE CORPORATION COMMISSION
8-19-91
AUG 19 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1800' of 4 1/2" casing
Conservation Division
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED
I (and my agent) observe this plugging.

DATE 8-28-91

Signed [Signature] (TECHNICIAN)

INV. NO. 32861