

1 090111

8-14 151-20,792-A 117 R  
API NUMBER 15-  
N/2 SW, SEC. 21, T. 26 S, R. 13 W/EX

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 30705  
Operator: B-Y Operating, Inc.  
Name & Address: 251 N. Water, Suite 10  
Wichita, KS 67202

1980 feet from S section line  
3960 feet from E section line

Lease Name Frisbee Well # C-2  
County Pratt 145.04  
Well Total Depth 4463 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635  
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 14 Month: 8 Year: 19 91

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4461' w/200 sx cement, PBTD 4404', Perfs at 3828-36, 3952-56'  
1st plug sand back to 3770' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:51 a.m. Day: 14 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3770' and dumped 4 sx cement on top of  
sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 100 sx cement.

Maximum pressure 100 psi and shut in 250 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
8-19-91  
AUG 19 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1940' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-28-91  
INV. NO. 32862

Signed [Signature] (TECHNICIAN)