

1 030782

JAN 17 1987

255
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,822 - 00-00
NW NW NW SEC. 18, T 26 S, R 13 W/E
4950 feet from S section line

TECHNICIAN'S PLUGGING REPORT

4700 feet from E section line

Operator License # 5435

Lease Name Bales B Well # 1

Operator: Bowers Drilling Company, Inc.
Name & Address 125 North Market
Wichita, KS 67202

County Pratt 140.60
Well Total Depth 4326 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 17 Month: 1 Year: 19 87

Plugging proposal received from Mike Waggoner

(company name) Red Tiger Drilling Company (phone) 913-625-7966
Elevation 1965'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 851-61'

1st plug at 850' with 50 sx cement, 2nd plug at 290' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 a.m. Day: 17 Month: 1 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 854' with 50 sx cement,

2nd plug at 305' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

INVOICED

DATE 2-9-87

INV. NO. 16095

Signed Steve Durrant
(TECHNICIAN)

REC'D
FEB 9 1987
CONSERVATION DIVISION
Wichita, Kansas