

1 030429

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,166 -00 R

NW NW SW, SEC. 14, T 26 S, R 13 W/X

2310 feet from S section line

4050 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Griffith Well # B-1

Operator: L. D. Davis

County Pratt 143.33

Name & Address

Well Total Depth 4410 feet

R. R. 1, Box 183B

Conductor Pipe: Size \_\_\_\_\_ feet

Great Bend, KS 67530

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing License Number 6901

Address Box 231, Claflin, KS 67525

Company to plug at: Hour: 9:30 am Day: 16 Month: May Year: 19 85

Plugging proposal received from Joe Strube

(company name) D S & W (phone) 316-587-3361

were: 4 1/2" at 4408' PBD 4250' Perfs at 3890-3894'

1st plug set CIBP at 3840' with 4 sx cement

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Robert B. Tarbutton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:10 am Day: 16 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3840' with 4 sx cement, 2nd plug squeezed

well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8"

rubber plug and pumped 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 17 1985

7-17-85  
CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 600 psi and shut in 400 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton. Recovered 2000' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Jack Pluchi observed the plugging  
did ~~(xxx)xxx~~ observe this plugging.

Signed Steve Burmont  
(TECHNICIAN)

INVOICE  
DATE 6-30-85  
8630  
INV. NO.