

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-151-21,682-00-00 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO Production Corp. OPERATORS LICENSE NO. 5171

ADDRESS 125 N. Market, Suite 1000, Wichita, KS 67202 PHONE # (316) 269-7600

LEASE (FARM) Kerr Estate "A" WELL NO. 2 WELL LOCATION 990' FNL 4290' FSL 4290' FEL COUNTY Pratt

SEC. 17 TWP. 29S RGE. 15 ~~(E) (W)~~ TOTAL DEPTH 4890' PLUG BACK TD 4869'

Check One:

OIL WELL XX GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 431' CEMENTED WITH 350 SACKS

CASING SIZE 5 1/2" SET AT 4889' CEMENTED WITH 125 SACKS

PERFORATED AT 4792' - 4802'

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Dump sand from PBD to 4750' followed by 5 sxs cement. Cut and pulling csg. Fill hole with mud to ±400'. Plug bottom of surface csg.

w/50 sxs 60-40 poz w/4 sxs hulls. Plug top w/10 sxs. Cut off surface ssg.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? YES
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Jerry Collins PHONE # (316) 886-5605 1987 RECEIVED
STATE CORPORATION COMMISSION
Rec'd
11-30-87

ADDRESS P.O. Box 125-B, R.R. #1, Medicine Lodge, KS 67104 CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR Great Bend Casing Pullers Inc. LICENSE NO. 4635CP 9/88

ADDRESS P.O. Box 768, Great Bend, KS 67530 PHONE # () 793-9711

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Cory West
(Operator or Agent)

DATE: Nov. 25, 1987

①

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

FEB 30 '88

EXPIRES

November 30, 1987

WELL PLUGGING NOTICE

Kerr Estate "A" #2
4290' FSL 4290' FEL
Sec. 17-29S-15W
Pratt County

TXO Production Corporation
125 N. Market, Ste. 1000
Wichita, KS 67202


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760