

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-151-21,662-00-00 (of this well) 6/88  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO Production Corp. OPERATORS LICENSE NO. 5171

ADDRESS 125 N. Market, Suite 1000, Wichita, KS 67202 PHONE # (316) 269-7600

LEASE (FARM) Kerr Estate "A" WELL NO. 1 THIS IS OK  
IT'S THE SAME LOCATION WELL LOCATION 330' FNL 4950' FSL 4950' FEL  
330' FNL COUNTY Pratt

SEC. 17 TWP. 29S RGE. 15 ~~W/4~~ (W) TOTAL DEPTH 4921(0)' PLUG BACK TO 4907'

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 371' CEMENTED WITH 300 SACKS

CASING SIZE 5 1/2" SET AT 4920' CEMENTED WITH 150 SACKS

PERFORATED AT 4800' - 10'

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Dump sand from PBD to 4750' followed by

5 sxs cement. Cut and pull casing. Fill hole with mud to ±400'. Plug bottom of surface csg.

w/50 sxs 60-40 poz w/4 sxs hulls. Plug top w/10 sxs. Cut off surface casing.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Yes  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Collins PHONE # (316) 886-5605

ADDRESS P.O. Box 125-B R.R. #1, Medicine Lodge, KS 67104

PLUGGING CONTRACTOR Great Bend Csq. Pullers Inc. LICENSE NO. 46356 RECEIVED  
CORPORATION COMMISSION  
7/88

ADDRESS P.O. Box 768, Great Bend, KS 67530 PHONE # (316) 793-9711 30 1987

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Cory West 11-30-87  
CONSERVATION DIVISION  
Operator or Agent, Kansas

DATE: Nov. 25, 1987

①

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

FEB 30 '88

EXPIRES

November 30, 1987

WELL PLUGGING NOTICE

Kerr Estate "A" #1  
4950'FSL 4950'FEL  
Sec. 17-29S-15W  
Pratt County

TXO Production Corporation  
125 N. Market, Ste. 1000  
Wichita, KS 67202


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760