

KANSAS

*sl*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 12 1969 5-12-69  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Independent Lease Management Company

Complete Address 800 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Freeman Well No. 3

Location C NE SE Sec. 6 Twp. 24 Rge. 10 (E) (W) X

County Reno Total Depth 3730'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Braden-Deem, Inc.

Address 210 One-Twenty Bldg., Wichita, Kansas License No. 580

Operation Completed: Hour 10 AM Day 4 Month May Year 1969

The above well was plugged as follows:

Hole filled with sand to 3690' and cemented with 5 sacks cement.

Rock bridge set from 260' to 250' and 5 sacks cement dumped on bridge and left to set over night. Hole bailed dry to 235' and cemented with 20 sacks cement (total 25)

Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *William D. Loman*  
Well Plugging Supervisor

DATE 5/14/69

INV. NO. 9743-W