

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSIONFEB 24 1966
2-24-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name The Dean-Clark Oil Company

Complete Address: Ambassador Suite, 305 Union Center Bldg., Wichita, Kans.

Lease Name Irvine Well No. # 1

Location C N/2 NE SW Sec. 30 Twp. 24 Rge. 11 (E) (W)W

County Stafford Total Depth 3927'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones, Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 11:30AM Day 21st Month Feb. Year 1966

The Above well was plugged as follows:

310' of 8 5/8" surface pipe, cement circulated with 275 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged with
hulls on fluid at 300', and cemented with 25 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls
on fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 2/24/66
INV. NO. 2995-W