

15.151-10722-00.00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAR 1 1965
3-1-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Z. K. Russell Well No. # 2

Location C NE SE SE Sec. 5 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4690'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 11:15AM Day 26th Month Feb. Year 1965

The Above well was plugged as follows:

420' of 8 5/8" surface pipe, cemented with 250 sacks. 4410' of 5 1/2" long
string, cemented with 250 sacks. Plug back to 4360'. Top perforation 3828'.
Plug was pushed to 3890', and 70' of sand, and bottom of the hole was cem-
ented with 5 sacks. 2830' of 5 1/2" long string was recovered from the hole.
Fluid in the hole was near the top. Bridge plug was pushed to 260', and
10' of rock bridge. 9 sacks of cement was mixed in barrel and put on plug
at 250', through the dump bailer, and let set over-night. Next morning
hole was bailed dry, and 16 sacks of cement was added to the plug. Hole was
filled with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/1/65

INV. NO. 746-W

Signed: Archie Elving
Well Plugging Supervisor