

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 26 1967

9-26-67

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Well Plugging Authority,  
issued July 20, 1967.

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St., Denver, Colorado 80203

Lease Name Zelma Kipp Russell Well No. # 1

Location SE Corn. of Lot 1 Sec. 5 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4284'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 4:00PM Day 21st Month Sept. Year 1967

The Above well was plugged as follows:

455' of 8 5/8" surface pipe, cemented with 250 sacks. 4284' of 5 1/2" long string,  
cemented with 200 sacks. Plug back T.D. 3963'. Top perforation 3804'. Bottom of  
the hole was sanded to 3750', and cemented with 20 sacks, with cement from 3750'  
to 3590'. 2496' of 5 1/2" long string was recovered from the hole. Bridge plug was  
pushed in fluid to 300', bridge plug and rock bridge from 300' to 290'. 6 sacks  
of cement with 8% Calcium Chloride was mixed in a barrel, and put on plug at 290',  
through the dump bailer, and let set for 2 hours. Hole was bailed dry and 19 sacks  
of cement was added to the plug. Hole was filled with mud to 40', rock bridge from  
40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audrie Elving  
Well Plugging Supervisor

INVOICED

DATE 9/26/67INV. NO. 6393-w