


 KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name Keller Well No. # 1

Location S/2 SE Sec. 24 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4403'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 10:30AM Day 26th Month June Year 1965

The Above well was plugged as follows:

485' of 8 5/8" surface pipe, cemented with 325 sacks. 4403' of 5 1/2" long
string, cemented with 175 sacks. Top perferation 3911'. Plug was pushed
to 3925', and 50' of sand bridge, and cemented with 5 sacks. 3310' of 5 1/2"
long string was recovered from the hole. Fluid level was up in the hole.
9 sacks of cement was mixed in barrel and put on bridge plug and rock
bridge at 260', through the dump bailer, and let set over-night. Next
morning hole was bailed dry, and 16 sacks of cement was added to the plug.
Hole was filled with mud to 40', and 10' of rock bridge, and cemented with
10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/28/65

INV. NO. 1368-W

Rec'd
6-28-65

Signed: Archie Elving
Well Plugging Supervisor