

15151-00303-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-3-66
AUG 3 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name Gobin Well No. # 1

Location SE SE SW Sec. 24 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4342'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 1:30AM Day 1st Month August Year 1966

The Above well was plugged as follows:

425' of 8 5/8" surface pipe, cemented with 275 sacks. 4337' of 5 1/2" long string, cemented with 100 sacks. Top perforation 4179'. Bottom of the hole was sanded to 4150', and cemented with 5 sacks, through the dump bailer. 3690' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 325', rock bridge from 325' to 315'. 5 sacks of cement was mixed in a barrel, and put on plug at 315', through the dump bailer, and let set over-week end. Hole was bailed dry, and 20 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED
DATE 8/3/66
INV. NO. 3686-u