

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
8-17-66
AUG 17 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name Gobin Well No. # 2

Location C W/2 SE SW Sec. 24 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4378'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 1:45PM Day 11th Month August Year 1966

The Above well was plugged as follows:

465' of 8 5/8" surface pipe, cemented with 325 sacks. 4377' of 5 1/2" long string, cemented with 150 sacks. Top perforation 4186'. Bottom of the hole was sanded to 4175', and cemented with 5 sacks, through the dump bailer. 3599' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 325', rock bridge from 325' to 315'. 5 sacks of cement was mixed in a barrel, and put on plug at 315', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 20 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 8/17/66

INV. NO. 3792-W