


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Reno County, Sec. 6 Twp. 24 Rge. 10 (E) W (W)
Location as "NE/CNW/SW" or footage from lines Center of SW of SW
Lease Owner Specter and Kornfeld
Lease Name Volker Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 11-11 19 42
Application for plugging filed yes Sept 25 19 54
Application for plugging approved yes Sept 27 19 54
Plugging commenced 12-10-54 19
Plugging completed 12-15-54 19
Reason for abandonment of well or producing formation Dry Not
commercially profitable
If a producing well is abandoned, date of last production about June 19 53
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Wren Horner
Producing formation Viola Depth to top 3734 Bottom 3751 Total Depth of Well 3751 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	267' 17"	none
				5 1/2 OD	3730'	3018 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Started 12-10-54 and completed 12-15-54. Measured in to TD 3751'.

Put in 30' of sand and 6 sacks of cement. Shot casing off at 3008'.

Pulled casing out of hole and filled hole with heavy mud to 250' and

set permanent rock bridge. Dumped in 15 sacks of cement and filled

hole from 200' with heavy mud to 35'. Mixed 10 sacks of cement for

cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company J. O. Forbes (owner)
Address P.O. Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Morton Specter

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Morton Specter*

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 1955

(Address)

My commission expires March 9, 1958

24-7366-B 3-53-20M

W. W. Dawson
RECEIVED Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 6 7 24 R 606
BOOK PAGE 67 LINE 2

JAN 4 - 1955
1-4-55
CONSERVATION DIVISION
Wichita, Kansas


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

AUTO-ORDNANCE CORP.
Otto Volker No. 1.

SEC.6 T.24 R.10 W
CSW SW

Total Depth. 3751'
Comm. 9-18-42 Comp. 11-11-42
Shot or Treated.
Contractor. Campbell & Kühn
Issued. 12-12-42

County. Reno



CASING:

8 5/8" 267'7"
5 1/2" 3730'

Elevation.

Production. Pot. 2940 B.
60 BW

Figures Indicate Bottom of Formations.

sand & gravel	150
red bed & shells	247
red rock	275
red bed, anhydrite, & red bed	518
red rock & shells	840
shale & shells	1040
salt & shells	1148
shale & shells	1353
red bed & shells	1500
lime bro.	1663
lime	1710
lime bro.	1795
lime & shale	1825
lime	2099
shale & shells	2210
lime bro.	2295
lime & shale	2389
shale & shells	2605
shale & lime	2756
	2829
lime	2970
lime & chert	3016
lime	3193
lime bro.	3267
lime shells	3301
lime	3407
lime & chert	3500
lime	3621
lime & shale	3668
lime	3695
shale	3718
Misener sand-layed down 88 jts drill pipe	3730
	3729- 3733
sand	3734
lime	3749
	3751

Total Depth.

Base Kansas City	3621
Top Conglomerate	3638
Top Kinderhook	3683
Top Misener Sand	3717
Top Viola	3734

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 - 1955

CONSERVATION DIVISION
Wichita, Kansas

