

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Reno County, Sec. 6 Twp. 24 Rge. 10 (E) W (W)
 Location as "NE/CNW/SW" or footage from lines Center NW of SW
 Lease Owner Specter and Knorfeld
 Lease Name Volker Well No. 2
 Office Address Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry
 Date well completed 11-11-42 19 42
 Application for plugging filed Sept 25 19 54
 Application for plugging approved Sept 27 19 54
 Plugging commenced 12-21-54 19
 Plugging completed 12-24-54 19
 Reason for abandonment of well or producing formation Dry Not
 commercially profitable
 If a producing well is abandoned, date of last production about June 19 53
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? yes

Name of Conservation Agent who supervised plugging of this well Rule Derky
 Producing formation Viola Depth to top 3756 Bottom 3758 Total Depth of Well 3758 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8 OD	266	none
				5 1/2 OD	3713	3124 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured in to TD 3758'. Filled back with sand and 6 sacks of cement. Shot casing off at 3100' and pulled pipe out of hole. Filled hole to 240' with heavy mud and set permanent rock bridge. Dumped in 25 sacks of cement with bailer. Filled hole with heavy mud to 30' of top and mixed 5 sacks of cement for cap on well. Plugging started 12-21-54 and finished 12-24-54.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company J. O. Forbes (owner)
 Address P. O. Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
 Morton Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Morton Specter*

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 1958

My commission expires March 9, 1958

(Address) *W. A. Dawson*
 Notary Public.

PLUGGING
 FILE SEC 6 T 24 R 10W
 BOOK PAGE 67 LINE 8

RECEIVED
 STATE CORPORATION COMMISSION
 1-4-58
 JAN 4 - 1958
 CONSERVATION DIVISION
 Wichita, Kansas


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

AUTO-ORDNANCE CORP.
Volker No. 2.

SEC. 6 T. 24 R. 10 W
GNW SW

Total Depth. 3758'
Comm. 10-13-42 Comp. 11-11-42
Shot or Treated.
Contractor.
Issued. 2-20-43

County. Reno



CASING:
8 5/8" 266' Cem.
5 1/2" 3713' Cem.

Elevation.

Production. Pot. 2550 B.,
450 BW, BHB

Figures Indicate Bottom of Formations.

surface loam, sand, gravel	101	Tops:
sand & gravel	165	Lansing 3340
red bed & shale	266	Cherty Conglomerate 3664
sand & gravel	310	Misener Sand 3712 1/2
red bed	485	Viola 3724
lime	540	
shale & lime	682	
shale & shells	1000	
shale, shells, salt	1225	
shale	1340	
shale & shells	1518	
lime, shale, sand	1650	
shale & lime	1800	
sand	1845	
brkn lime & shale	1895	
lime & shale	1920	
sly lime & shale	2310	
shale & shells	2575	
lime & shale	2740	
lime (Topeka)	2870	
lime	3140	
lime & shale	3250	
lime K.C.	3296	
lime brkn	3370	
lime	3423	
chert	3428	
lime	3430	
lime & chert	3464	
lime & shale	3545	
lime	3597	
lime & little chert	3628	
lime, hd cherty	3679	
shale	3712 1/2	
sand	3722	
sand sft	3733	
sand hd	3740	
lime medium	3749	
lime	3756	
lime sft	3758	
Total Depth.		

PLUGGING
WEL SEC 6 T 24 R 10 W
BOOK PAGE 67 LINE 8

RECORDED
COMMISSIONER
DIVISION
Wichita, Kansas