


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Reno County, Sec. 6 Twp 24S Rge. (E) 10 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines CNW NW
Lease Owner Magnolia Petroleum Company
Lease Name Newt Darr Well No. 2
Office Address Box 770, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry-Hole) Oil
Date well completed Feb. 25 19 43
Application for plugging filed May 3, 19 51
Application for plugging approved May 4, 19 51
Plugging commenced May 14, 19 51
Plugging completed May 21, 19 51
Reason for abandonment of well or producing formation well did not produce enough oil to pay to operate
If a producing well is abandoned, date of last production April 19 51
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee
Producing formation Viola lime Depth to top 3700 Bottom 3774 Total Depth of Well 3790 TD Feet
PB.TD 3774'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola	Oil	3700	3774	10-3/4	350	None
				5-1/2	3700	2977

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged btm hole w/rock from 3774' to 3690' & 6 sx cem 3690' to 3672'. Shot @ 3100'; & shot off 5-1/2" csg @ 2986' & pulled 2977' of 5-1/2" csg. Filled w/heavy mud to 300' & set rock bridge plug @ 300' & cemented w/20 sx cem to 240' & filled w/heavy mud to 15' & cemented base of cellar w/5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. C. A. Hill, Magnolia Petroleum Company
Address Box 770, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
C.A. Hill - Magnolia Petroleum Company (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C.A. Hill*
Box 770, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28 day of May 19 51
Notary Public

My commission expires Oct. 15, 1953 22-7877-s 4-49-10M

PLUGGING
FILE SEC 6 T 24 R 10 W
BOX PAGE 79 LINE 2

MAGNOLIA PETROLEUM COMPANY

NEWT DARR #2
 CNW NW, Sec. 6-24S-10W
 Reno County, Kansas

LOG OF WELL

PLUGGING STARTED: May 14, 1951
 PLUGGING COMPLETED: May 21, 1951

CASING RECORD	PUT IN	PULLED OUT
10-3/4"	350	None
5-1/2"	3700	2977

Well Plugged & Abd. by: Standard Pulling Co., Lyons, Kansas

Elev: 1810'

FORMATION	TOP	BOTTOM
Red rock & sand	0	160
Red rock & shells	160	360
10-3/4" csg set	350	
Red rock & shale	360	940
Shale & salt	940	1230
Shale & shells	1230	1695
Lime & shale	1695	1790
Lime	1790	1950
Lime & shale	1950	2270
Shale	2270	2415
Shale & lime	2415	2770
Lime	2770	2820
Shale	2820	2965
Lime	2965	3000
Shale	3000	3190
Lime	3190	3270
Shale & lime	3270	3370
Lime	3370	3540
Shale & lime	3540	3580
Lime	3580	3615
Lime & shale	3615	3696
Top Misener sand	3693	
Misener sand	3693	3696
Sylvan shale	3696	3700
Top Viola lime	3700	
Viola lime	3700	3701
5-1/2" csg set	3700	
Viola lime	3701	3734

COMPLETION HISTORY

Acid w/4000 gals acid thru 2 1/2" tubing, Potential 3292 bbl. by BHPG - flowing 2/25/43.
 1-13-47 DD from 3734 to 3790 & PB to 3774 w/2 sx cement.

PLUGGING RECORD:

Plugged btm hole w/rock from 3774' to 3690' & 6 sx cem 3690' to 3672'. Shot @ 3100'; & shot off 5-1/2" csg @ 2986' & pulled 2977' of 5-1/2" csg. Filled w/heavy mud to 300' & set rock bridge plug @ 300' & cemented w/20 sx cem to 240' & filled w/heavy mud to 15' & cemented base of cellar w/5 sx cement.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 29 1951
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 6-24-10W
 BOOK PAGE 79 LINE 22

MAGNOLIA PETROLEUM COMPANY

NEWT DARR #2
 CNW NW, Sec. 6-24S-10W
 Reno County, Kansas

LOG OF WELL

PLUGGING STARTED: May 14, 1951
 PLUGGING COMPLETED: May 21, 1951

CASING RECORD
 10-3/4
 5-1/2

PUT IN PULLED OUT
 350 None
 3700 2977

Well Plugged & Abd. by: Standard Pulling Co., Lyons, Kansas

Elev: 1810'

FORMATION	TOP	BOTTOM
Red rock & sand	0	160
Red rock & shells	160	360
10-3/4" csg set	350	
Red rock & shale	360	940
Shale & salt	940	1230
Shale & shells	1230	1695
Lime & shale	1695	1790
Lime	1790	1950
Lime & shale	1950	2270
Shale	2270	2415
Shale & lime	2415	2770
Lime	2770	2820
Shale	2820	2965
Lime	2965	3000
Shale	3000	3190
Lime	3190	3270
Shale & lime	3270	3370
Lime	3370	3540
Shale & lime	3540	3580
Lime	3580	3615
Lime & shale	3615	3696
Top Misener sand	3693	
Misener sand	3693	3696
Sylvan shale	3696	3700
Top Viola lime	3700	
Viola lime	3700	3701
5-1/2" csg set	3700	
Viola lime	3701	3734

COMPLETION HISTORY

Acid w/4000 gals acid thru 2 1/2" tubing, Potential 3292 bbl. by BHPG - flowing 2/25/43.
 1-13-47 DD from 3734 to 3790 & PB to 3774 w/2 sx cement.

PLUGGING RECORD:

Plugged btm hole w/rock from 3774' to 3690' & 6 sx cem 3690' to 3672'. Shot @ 3100'; & shot off 5-1/2" csg @ 2986' & pulled 2977' of 5-1/2" csg. Filled w/heavy mud to 300' & set rock bridge plug @ 300' & cemented w/20 sx cem to 240' & filled w/heavy mud to 15' & cemented base of cellar w/5 sx cement.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 29 1951
 CONSERVATION DIVISION
 Wichita, Kansas