

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County, Sec. 30 Twp. 24 Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE-NE-SW  
Lease Owner Cooperative Refinery Association- Rex Morris  
Lease Name Irvine "B" Well No. 1  
Office Address Box 765 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed March 15 19 55  
Application for plugging filed March 15 19 55  
Application for plugging approved March 16 19 55  
Plugging commenced March 15 19 55  
Plugging completed March 15 19 55  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well N. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3921 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	310	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled up hole with heavy mud to 275'. Set plug at 275', cemented with 20 sx. Set plug at 35', cemented with 10 sx. to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Cooperative Refinery Association  
Address Box 765 Great Bend, Kansas

Rec'd  
3-17-55

STATE OF KANSAS, COUNTY OF BARTON, ss.  
P. H. Jackson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. H. Jackson  
Box 765 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of March, 19 55

Donald C. Hunt  
Notary Public.

My commission expires August 17, 1957

PLUGGING  
FILE DEC 30 1955  
BOOK PAGE 104 LINE 8

DRILLERS LOG

Irvine "B" #1

Loc: NE-NE-SW  
 Sec: 30-24-11W  
 Stafford County, Kansas  
 Operator: Cooperative Refinery Ass'n.  
 Contractor: Co. Rig #5

Elevation: 1838 D.F.  
 Casing: 8 5/8" @ 310' w//  
 200 sx.

Comm: 3-1-55 Comp: 3-15-55  
 Total Depth: 3921 R.T.D.

<u>From</u>	<u>To</u>	<u>Formation</u>
0	190	Surface hole
190	310	Shale, shells, redbed
310	625	Red Bed, shale
625	1590	Shale & shells
1590	2180	Shale & Lime
2180	2330	Shale, lime, shells
2330	3160	Lime & shale
3160	3225	Lime
3225	3285	Lime & Shale
3285	3330	Lime
3330	3480	Shale & Lime
3480	3911	Lime
3911	3921	Lime & Chert
3921		R.T.D.

(STATE OF KANSAS )

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Irvine "B" #1 well, located NE-NE-SW of Section 30-24-11W, Stafford County, Kansas

P. H. Jackson

Subscribed and sworn to before me this 16 day of March 1955

Donald E. Hunt

My Commission Expires: August 17, 1957

PLUGGING  
 FILE SEC 30-24-11W  
 DECK PAGE 104 LINE 8