


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 30 Twp. 24 Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE
Lease Owner National Cooperative Refinery Association
Lease Name Minks Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 20, 1957
Application for plugging filed June 13, 1957
Application for plugging approved June 14, 1957
Plugging commenced 19
Plugging completed August 8, 1957
Reason for abandonment of well or producing formation Depletion - Well went to water.
If a producing well is abandoned, date of last production June 20, 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3905 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	314'	None
				5 1/2"	3901'	3513'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back from 3905' to 3890' with sand. Plugged back to 3850' with 5 sacks of cement. Shot 5 1/2" casing off at 3513'. Pulled to 900', circulated 20 sacks of mud. Pulled pipe. Set rock bridge at 240' / 20 sacks of cement. Mudded hole to 15', set rock bridge / 5 sacks of cement on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor A.C.E. Pipe Pulling Company
Address Box 304, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. C. R. Sears (employee of owner) or (~~owner~~ / ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. R. Sears C. R. Sears
305 Rule Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 12th day of August, 1957
Nell McComb Notary Public.

My commission expires November 26, 1960.

PLUGGING
FILE SEC 30 T. 24 R. 11W
BOOK PAGE 20 LINE 20

RECEIVED
8-13-57
AUG 13 1957
CONSERVATION DIVISION
Wichita, Kansas

D R I L L E R ' S L O G

National Cooperative Refinery Association
Minks #1
NE NW SE 30-24-11
Stafford County, Kansas

<u>TO</u>	<u>FROM</u>	
0	120	Surface Clay & Sand
120	145	Sand
145	318	Shale, Shells & Red Rock
318	608	Red Bed & Shale
608	623	Anhydrite
623	675	Shale & Shells
675	1575	Shale, Shells & Salt
1575	1805	Lime & Shale
1805	1905	Lime
1905	2450	Lime & Shale
2450	2770	Shale & Lime
2770	2845	Shale & Shells
2845	3000	Shale & Lime
3000	3095	Lime & Shale
3095	3295	Lime
3295	3534	Lime & Shale
3534	3638	Lime
3638	3690	Lime, Chert & Shale
3690	3815	Lime & Shale
3815	3902	Shale & Lime
	3902	ROTARY TOTAL DEPTH

COMMENCED: 2-28-55
COMPLETED: 3-12-55

CASING RECORD:

Set 314.64' of 8 5/8" surface casing with 200 sacks cement.
Set 5 1/2" casing with 75 sacks of cement - Set at 3901'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Minks #1 located NE NW SE of Section 30-24-11, Stafford County, Kansas.

ANSCHUTZ DRILLING CO., INC.

BY:

E. G. Koelling
E. G. Koelling

Subscribed and sworn to before me this 15th day of March, 1955.

Charlenne Barber
Notary Public

My Commission Expires: July 28, 1958.

RECEIVED
NOTARY COMMISSION

RECEIVED
A. H. C. M.
ATTORNEY
3281 S. I. ST.

PLUGGING
FILE SEC. 30 T. 24 N. 11W
BOOK PAGE 20 LINE 20

JUN 14 1957
MINING DIVISION
Topeka, Kansas