

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-151-21,690-00-08

LEASE NAME Howell

WELL NUMBER 2-17 SWD

         Ft. from S Section Line

         Ft. from E Section Line  
 SW 1/4

SEC. 17 TWP. 29S RGE. 15 (E) or (W)

COUNTY Pratt

Date Well Completed         

Plugging Commenced 11-19-90

Plugging Completed 11-23-90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR FARRAR PUMP & SUPPLY, INC.

ADDRESS 54/281 jct. Medicine Lodge, Ks. 67104

PHONE# (316) 886-3763 OPERATORS LICENSE NO. 3399

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 5800

PBTD 5145 Perfs: 4827-4832 5145-5804, 700' of open hold. 4020' top of cement.  
 Show depth and thickness of all water, oil and gas formations. ..

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	448	8 5/8	448	0
			5145	5 1/2	5145	3595'; 86 jts.
				2 7/8		149 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from          feet to          feet each set  
 To location: Rigged up and pulled 149 jts. of 2 7/8" tubing, Dia Log shot off casing at 3595'. Recovered 86 jts. of casing. Dumped sand and cement to cover perfs for bottom hole plug. BI Titan top hole plug: 75 sx, 60/40 poz: 2774# 6% gel; 400# hulls; one 8 5/8 plug.  
12-3-90: 46 ft down to top of cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address North Highway 61 Pratt, Kansas 67124 RECEIVED  
STATE CORPORATION COMMISSION  
1-2-91  
JAN 2 1991

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: FARRAR PUMP & SUPPLY

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry


plugging contractor

(Employee of ~~Operator~~ ~~Operator~~ ~~Operator~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed there. The same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO Box 847 - Pratt, Ks. 67124



SUBSCRIBED AND SWORN TO before me this 26th day of December, 1990

Dorothy M. Furgason  
 Notary Public

My Commission Expires February 6, 1993