

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,859 - 00-0A

LEASE NAME Perdue

WELL NUMBER #1 "B"

2310 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 17 TWP. 29 RGE. 15 ~~W~~(W)

COUNTY Pratt

Date Well Completed 10-29-87

Plugging Commenced 10-29-87

Plugging Completed 10-29-87

LEASE OPERATOR Raymond Oil Company, Inc.

ADDRESS PO Box 48788, Wichita, KS 67201

PHONE#(316) 267-4214 OPERATORS LICENSE NO. 5046

Character of Well \_\_\_\_\_

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #1 - Dodge City - Durrant, Steve

Is ACO-1 filed? will be by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4932'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Plug #1 set at 930' with 50 sacks cement through drill pipe  
Plug #2 set at 360' with 40 sacks cement through drill pipe  
Plug #3 set at 40' with 10 sacks cement; 15 sacks in rat hole; fill water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address PO Box 823, Great Bend, KS 67530


STATE OF KANSAS COUNTY OF BARTON, ss.

John Armbruster (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Armbruster  
(Address) PO Box 823, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 2 day of November, 1987

Dorothy M Hague  
Notary Public



DRILLER'S WELL LOG

DATE COMMENCED: October 20, 1987  
 DATE COMPLETED: October 29, 1987

Raymond Oil Company, Inc.  
 Perdue #1 "B"  
 N/2 NW SE  
 Sec. 17-T29S-R15W  
 Pratt County, KS

0 - 930' Surface Soil, Red Bed, Sand  
 930 - 952' Anhydrite  
 952 - 3570' Shale, Lime  
 3570 - 3948' Lime  
 3948 - 3953' Shale  
 3953 - 4122' Lime, Shale  
 4122 - 4504' Lime  
 4504 - 4800' Shale, Lime, Chert  
 4800 - 4830' Shale  
 4830 - 4908' Simp. Dolomite, Lime  
 4908 - 4932' Dolomite  
 4932' RTD

ELEVATION: 2047 K.B.

FORMATION DATA

Anhydrite	930-952
Topeka	3570
Heebner	3948
Brown Lime	4109
Lansing	4122
Base KC	4504
Mississippi	4629
Viola	4752
Simpson Shale	4800
Simpson Dolo.	4830
Arbuckle	4908
RTD	4932

Surface Pipe: Set new 8-5/  
 20# pipe at 333' with 250  
 sacks 60/40 pozmix with  
 2% gel, 3% c.c.

A F F I D A V I T


STATE OF KANSAS  
 COUNTY OF BARTON) ss

JOHN ARMBRUSTER of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*John Armbruster*  
 John Armbruster

SUBSCRIBED AND SWORN to before me this 3rd day of November, 1987.

*Dorothy M. Hague*  
 Notary Public



RECEIVED  
 STATE CORPORATION COMMISSION

NOV 4 1987

CONSERVATION DIVISION  
 Wichita, Kansas