

15-151-2616-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NOT AVAILABLE

LEASE NAME Howell

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-18

 Ft. from S Section Line

 Ft. from E Section Line
NE 1/4

SEC. 18 TWP. 29S RGE. 15 ~~XWB~~ or (W)

COUNTY Pratt

LEASE OPERATOR FARRAR PUMP & SUPPLY, INC.

ADDRESS 54/281 jct. Medicine Lodge, Kansas 67104

PHONE#(316) 886-3763 OPERATORS LICENSE NO. 3399

Date Well Completed

Character of Well Oil

Plugging Commenced 10-30-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-1-90

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 5302

Show depth and thickness of all water, oil and gas formations. PBTD 4708'; Perfs: 4752-56

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	450	8 5/8	450	0
			5154	5 1/2	5154	3155'--75 jts.
				3/4 & 7/8		82x7/8; 61x3/4; 18x7/8
				2 7/8		129 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
To location: Rigged up, pulled rods, pump and tubing out of well. Ran measuring line, TD at 4830'. Dumped sand, water, 5 sx. cement for bottom hole plug. Shot off casing and pulled 3155 jts. of casing. BI Titan plugged top hole with 75 sx. 60/40 poz; 2774# 6% gel; 400# hulls; 8 5/8 wiper plug. 12 2 90 cement to top of hole.
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRAIT WELL SERVICE, INC. License No. 5893


Address North highway 61 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Farrar Pump & Supply, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry plugging contractor (Employee/ ~~operator~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.



(Signature) Judy Berry
(Address) PO Box 847 - Pratt, Ks. 67124

SUBSCRIBED AND SWORN TO before me this 26th day of December, 19 90

Dorothy M. Ferguson
Notary Public

My Commission Expires February 6, 1993