

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,952-0D-0D

LEASE NAME Frisbie

TYPE OR PRINT

WELL NUMBER 4

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310 Ft. from S Section Line

4290 Ft. from E Section Line

LEASE OPERATOR Quinoco Petroleum, Inc.

SEC. 5 TWP. 26 RGE. 13 (E or W)

ADDRESS P.O. Box 378111 Denver, CO 80237

COUNTY Pratt

PHONE#(316) 792-2756 OPERATORS LICENSE NO. 3613

Date Well Completed 11-14-89

Character of Well D&A

Plugging Commenced 11-14-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-14-89

The plugging proposal was approved on 11-10-89 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4510'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Bottom Plug: @ 4410' w/40 sacks cement thru drill pipe  
 Next Plug: @ 870' w/50 " " " " "  
 Next Plug: @ 330' w/40 " " " " "  
 Top Plug: @ 40' w/10 " " " " " 15 sacks in Rat Hole  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Quinoco Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530



SUBSCRIBED AND SWORN TO before me this 20 day of November, 19 89

Dorothy M. Hague  
Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: November 3, 1989  
DATE COMPLETED: November 14, 1989

Quinoco Petroleum, Inc.  
FRISBIE #4  
NE NW SW  
Sec. 5, T26S, R13W  
Pratt County, Ks.

0 - 208' Surface Soil, Clay, Sand  
208 - 855' Red Bed  
855 - 886' Anhydrite  
886 - 2155' Shale  
2155 - 2835' Lime & Shale  
2835 - 4510' Lime  
4510' RTD

ELEVATION: 1951 K.B.

Surface Pipe: Set new  
8-5/8", 23# pipe @302'  
w/150 sacks 60/40 pozmix  
2% gel 3% cc. & 150 sacks  
60/40 pozmix 3% cc.

A F F I D A V I T


State of Kansas  
County of Barton) ss

Leonard Williamson of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 20 day of November 1989.

*Dorothy M. Hague*  
Notary Public



RECEIVED  
STATE CONSERVATION COMMISSION

11/27/1989

CONSERVATION DIVISION  
Wichita, Kansas