

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-151-22139 - 00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Marmik Oil Company OPERATORS LICENSE NO. 6875 *9/96*

ADDRESS 200 N. Jefferson, #500, El Dorado, AR 71730 PHONE # (501) 862-8546

LEASE (FARM) Blackburn WELL NO. 2 WELL LOCATION NE SE SW COUNTY Pratt

SEC. 7 TWP. 26 RGE. 11 (E) or  (W) TOTAL DEPTH 4273 PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A  SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 10 3/4 SET AT 253 CEMENTED WITH 195 SACKS

CASING SIZE 4 1/2 SET AT 4255 CEMENTED WITH 165 SACKS

PERFORATED AT 4070-90

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Fill w/sand to 4020, 4 sx cmt on top of

sand, pull pipe, pump down 10 3/4" w/400# cottonseed hulls and 20 sx of gel, 10 3/4 wiper plug

and 200 sx of cmt 60/40 poz 6% gel

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no

(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1-4-96

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Curtis G. Morrill PHONE # (501) 862-8546

ADDRESS 200 N. Jefferson #500, El Dorado, AR 71730

PLUGGING CONTRACTOR Pratt Well Service LICENSE NO. 58936/96

ADDRESS Pratt, Kansas PO BOX 847 PHONE # (314) 672-2531

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Curtis Morrill

(Operator or Agent)

DATE: December 21, 1995



## Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Timothy E. McKee, Commissioner  
Judith McConnell, Executive Director

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

December 27, 1995

Marmik Oil Company  
200 N Jefferson #500  
El Dorado AR 71730

Blackburn #2  
API 15-151-22,139  
NE SE SW  
Sec. 07-26S-11W  
Pratt County

Dear Curtis G. Morrill,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
Daxian P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760