

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-22549-00-00
Spot: SWSENWNW Sec/Twnshp/Rge: 14-34S-4E
3990 feet from S Section Line, 4440 feet from E Section Line
Lease Name: OWEN CRAIN Well #: 8
County: COWLEY Total Vertical Depth: 3210 feet

Operator License No.: 3661
Op Name: GROVES, PHIL DBA PHIL GROVES OIL
Address: 811 E MADISON AVE PO BOX 571
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3100		
COND	4.5	3204	1100	
PROD	4.5	3209	1106	125 SX
SURF	8.625	201		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2015 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: PHIL GROVES Company: PHIL GROVES OIL Phone: (620) 442-0480

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/23/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3100', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL 3% CC & DISPLACED IN CASING. LAYED DOWN TUBING. TAGGED CEMENT PLUG @ 3045'. CASING WAS PARTED @ 1106' 36 JOINTS OF 4 1/2" CASING. RIH W/TBG @ 320'. CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 112 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/14 SXS. CEMENT TICKET #51159.

Perfs:

Top	Bot	Thru	Comments
3174	3178		CSG

Remarks: TA LETTERS/ COMPLIANCE/ 10 YEAR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)
KCC WICHITA

FEB 08 2016

RECEIVED

2-8-2016

Form CP-2/3

No 29-16

✓