

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22451-00-00
Spot: W2SESESE Sec/Twnshp/Rge: 12-32S-4W
330 feet from S Section Line, 400 feet from E Section Line
Lease Name: BRUCE Well #: 3
County: SUMNER Total Vertical Depth: 4434 feet

Operator License No.: 32346
Op Name: B5 OPERATING, LLC
Address: PO BOX 45
WELLINGTON, KS 67152

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2460		
PROD	5.5	3117		215 SX
SURF	8.625	274		160 SX
TI	2.375	2117		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/16/2011 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: MITCHEL BARTELSON Company: B5 OPERATING LLC Phone: (326) 048-6620

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 03/18/2011 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET A TB 2200' AND CAPPED WITH 2 SKS OF CEMENT. THE CASING WAS PERFORATED AT 650', AND CEMENT WAS CIRCUALTED TO SURFACE. LET SET OVER NIGHT. CEMENT FELL. RAN 1" TUBING TO 300' AND CIRCUALTED CEMENT BACK TO SURFACE INSIDE THE 5.5 RAN 1 INCH TUBING BETWEEN THE 5.5 AND 8.625 AND CIRCUALTED CEMENT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3029	3032	CSG	
3027		CSG	
3019	3022	CSG	
2550		CSG	
2497	2503	CSG	
2460		CSG	
2100	2104	CSG	
2082	2086	CSG	

Remarks: CONSOLIDATED OIL WELL SERVICES COMMON CEMENT.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)
KCC WIC...

FEB 03 2016

RECEIVED

2-8-2016

Form CP-2/3

no
2-9-16

1/24