

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21064-00-00

LEASE NAME Schlenz

WELL NUMBER 1

SPOT LOCATION SW - SW - SW

SEC. 6 TWP. 26S RGE. 11 (E or W)

COUNTY Pratt

Date Well Completed 2/13/84

Plugging Commenced 2/3/84

Plugging Completed 2/13/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR American petrofina Co. of Texas

ADDRESS 4613 Jacksboro HY. - Wichita Falls, TX

PHONE # ( ) OPERATORS LICENSE NO. X 5692

Character of Well Dry  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Paul Luthi

Is ACO-1 filled? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4377

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	350	none
				5 1/2	4375	2660

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. plug Bakar 4210 CLBP with sand from 4210 to 4080  
5 sacks cement with dump Bailer from 4080 to 4050

Repeat at 300 and 2800 to 2660 Halliburton pumper pump in 2 sacks hulls 10 sacks of jell 50 sacks of cement 10 sacks of jell 1 sacks hulls drop plug 125 sacks cement 60 sacks POZ  
If additional description is necessary, use BACK of this form. ) 2% jell 3% CC

Name of Plugging Contractor Clarke Corp. License No. 5105  
Address P O Box 187 - Medicine Lodge, KS 67104

2-23-84

STATE OF Kansas COUNTY OF Barber, ss.

RECEIVED  
STATE CORPORATION COMMISSION

Elmo Morgenstern (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

FFR 23 1984

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) \_\_\_\_\_

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 22 day of February, 1984

Pamela Rieke  
Notary Public

My Commission expires: 10-11-87

R. T. WOODMAN  
RES. PHONE 738-0418  
OFF. PHONE 265-7650  
WICHITA, KANSAS

D. J. IANNITTI  
PHONE 792-2921  
GREAT BEND, KANSAS

## WOODMAN & IANNITTI DRILLING COMPANY

*Rotary Drilling Contractors*

1008 DOUGLAS BUILDING  
104 S. BROADWAY  
WICHITA, KANSAS 67202

January 21, 1982

Company: American Petrofina Co. of Texas  
Farm: #3 Schlenz  
Location: SW SW SW  
Section: 6-26S-11W  
County: Pratt  
Contractor: Woodman & Iannitti Drilling Co.  
Comm.: January 9, 1982  
Comp.: January 20, 1982  
Total Depth: 4375'  
Casing: 8-5/8", 373' w/225 sx.

### Figures Indicate Bottom Formations:

30	Clay
140	Sand
374	Shale
410	Red Bed
1077	Shale
1680	Shale
1840	Shale & Lime
2098	Shale & Lime
2240	Shale & Lime
2405	Shale & Lime
2580	Shale & Lime
2721	Shale & Lime
2883	Shale & Lime
3050	Shale & Lime
3242	Shale & Lime
3410	Shale & Lime
3540	Shale & Lime
3640	Lime & Shale
3745	Lime
3832	Lime
3906	Lime
4001	Lime
4055	Lime
4112	Lime
4145	Lime
4163	Viola
4224	Lime & Shale
4285	Lime & Shale
4300	Shale & Arbuckle
4353	Arbuckle
4375	Arbuckle

RECEIVED  
STATE CORPORATION COMMISSION

JAN 25 1984

CONSERVATION DIVISION  
Wichita, Kansas

I certify the above to be a true and correct copy of the drillerslog to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.  
*K.T. Woodman*  
K.T. Woodman, Partner