

LEASE NAME Bookstore

WELL NUMBER 1-6

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 6 TWP 26 SRGE. 11 W(E) or (W)

COUNTY Pratt

Date Well Completed         

Plugging Commenced 6-8-89

Plugging Completed 6-19-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR W. L. Kirkman, Inc.

ADDRESS P.O. Box 782290 Wichita, KS. 67278-2290

PHONE# (316) 685-5372 OPERATORS LICENSE NO. 5673

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4113

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	363	none
				4 1/2	4110	2800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Plugged bottom with sand to 2934', dumped down 4 sacks cement, shot @ 2800'. Plugged surface w/ 400# hulls, 10 gal, 50 sacks cement, 10 gal, 100# hulls, 100 sacks cement 60/60 gel, 20 sacks gel, 500 # hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: W. L. Kirkman, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 21 day of July, 19 89

Jane Hoover  
 Notary Public

My Commission Expires:



ALDEBARAN

453 SOUTH WEBB ROAD  
P.O. BOX 18611  
WICHITA, KANSAS 67207  
(316) 685-5372



DRILLING CO. INC.

WELL LOG

WELL NAME: ██████████

WELL LOCATION: C SE-NW  
SEC. 6-26S-11W PRATT COUNTY, KS.

COMMENCED: 5:00 P.M. 11-5-84

COMPLETED: 7:00 A.M. 11-15-84

OPERATOR: W.L. KIRKMAN, INC.

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

9 jts. 8 5/8" 23 new set at 363'  
CASING RECORD: 300 sks. common 3% cc.  
2% gel. - 107 jts. 4 1/2" 10.5 wt.  
used set at 4110' 325 sks. 60-40  
poz. 18% salt 3/4 of 1% D-31  
w S10 1000 gal. DJ mud sweep

FORMATION:

Sand-Red Bed  
Red Bed  
Lime-Shale  
Shale  
Viola

FROM:

0  
375'  
1719'  
4090'  
4110'

TO:

375'  
1719'  
4090'  
4110'  
4113'

RECEIVED  
STATE CORPORATION COMMISSION  
APR 5 1989  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED  
C SE-NW, SEC. 6-26S-11W, Pratt County, Kansas TO THE BEST OF MY

KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.  
WAYNE L. KIRKMAN  
PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 20TH DAY OF NOVEMBER, 1984

APPOINTMENT EXPIRES MARCH 20, 1987

*Kathleen G. Quinn*  
KATHLEEN G. QUINN