

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County. Sec. 6 Twp 26S Rge. (E) 11 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/4 SE/4 SW/4

Lease Owner Skelly Oil Company

Lease Name John G. Schlenz Well No. 1

Office Address Box 1650, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 15, 1950

Application for plugging filed September 18, 1950

Application for plugging approved September 18, 1950

Plugging commenced September 17, 1950

Plugging completed September 17, 1950

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (verbally)

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough

Producing formation none Depth to top Bottom Total Depth of Well 4338 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	OD Size	Put In	Pulled Out
Viola Lime	Dry	4133'	4230'	8-5/8"	427'0"	None
Arbuckle Lime	Dry	4313'	4338'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

75 sacks of cement 4338' to 4089'
Mud laden fluid 4089' to 540'
30 sacks of cement 540' to 450'
Mud laden fluid 450' to 100'
30 sacks of cement 100' to 6'
Surface soil 6' to 0'

9-23-50

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Skelly Oil Company
Address Box 391 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno

H. E. Wamsley (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 391, Hutchinson, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1950.

My commission expires April 7, 1951

Notary Public

PLUGGING
FILE SEC. 6-T-26R-11W
BOOK PAGE 28 LINE 28