

15-155-00141-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Reno County, Sec. 34 Twp. 22 Rge. 10 (E) W(W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner M. B. Armer

Lease Name Tretbar Well No. 1

Office Address 710 Petroleum Bldg.; Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 7 19 53

Application for plugging filed April 6 19 53

Application for plugging approved April 6 19 53

Plugging commenced April 6 19 53

Plugging completed April 6 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3730 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud from T.D. to 250'. Set wood plug @250' bridged with hulls and cemented with 15 sacks cement.

Filled hole with extra heavy drilling mud from 250' to 40' and set plug cemented with 5 sacks cement on top of plug.

STATE CORP. COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
4-28-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 1005 Central Bldg.; Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Prime Drilling Company (drilling contractor)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) BY: J. J. Campbell Prime Drilling Company

(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of April, 19 53

My commission expires October 29, 1955

24-2675-B 2-52-20M

PLUGGING
FILE SEC 34 T 22 R 10W
BOOK PAGE 21 LINE 34

ROTARY DRILLING LOG

Operator: M. B. Arner
Trotbar #1
SE SE SE Sec. 34-22-10W
Reno County, Kansas

Contractor:
Prime Drilling Co.

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand, Shale & Shells	0	70	
Sand	70	130	
Sand, Clay & Red bed	130	250	
Red bed & Shells	250	300	8 5/8" csg. set
Shale & Red bed	300	550	@ 250' cemented
Shale & Shells	550	1590	with 150 sacks
Shale & Lime	1590	3215	cement & 2cc.
Lime	3215	3585	
Dolomite & Colg.	3585	3600	
Chert & Shale	3600	3615	
Chert	3615	3640	
Chert, Shale & Colg.	3640	3670	
Lime	3670	3730	
Total Depth		3730	

We certify that the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

By C. A. Trichard
President

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1953 4-28-53
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 34 T 22 R 10 W
BOOK PAGE 21 LINE 34