

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

RENO County, Sec. 34 Twp. 22S Rge. (E) 10 (W)  
Location as "NE/CNW/SW" or footage from lines. NE NE NW  
Lease Owner REX & MORRIS DRILLING COMPANY AND E. H. RIGGS  
Lease Name WADDLE Well No. 1  
Office Address P. O. BOX 334, EL DORADO, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 5 JUNE 1963  
Application for plugging filed 5 JUNE 1963  
Application for plugging approved 5 JUNE 1963  
Plugging commenced 5 JUNE 1963  
Plugging completed 5 JUNE 1963  
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production NONE 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GILBERT J. TOMAN  
Producing formation NONE Depth to top Bottom Total Depth of Well 3720 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE HOLE	WATER	SURFACE	213' RB	8 5/8" OD	207.81	LEFT IN
(SEE ATTACHED LOG)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE TO 200' WITH DRILLING MUD, SET PLUG AND CEMENTED WITH 20 SACKS CEMENT, FILLED HOLE WITH DRILLING MUD TO 35', SET PLUG AND CEMENTED WITH 10 SACKS CEMENT, PUT 2 SACKS CEMENT IN RAT HOLE.

RECEIVED  
STATE CORPORATION COMMISSION  
10-22-63  
OCT 22 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor REX & MORRIS DRILLING COMPANY  
Address P. O. BOX 334, EL DORADO, KANSAS

STATE OF KANSAS, COUNTY OF BUTLER, ss.  
A. H. FISHER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Fisher  
P. O. BOX 334, EL DORADO, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 6TH day of JUNE 1963  
Mary Bailey  
MARY BAILEY Notary Public.

My commission expires 28 JULY 1963

15-155-02078-0000

ELEVATION: 1758' RB  
1755' DEWADDELE #1REX & MORRIS DRILLING COMPANY AND E. H. RIGGS

TOTAL DEPTH 3720'  
 CONTRACTOR REX & MORRIS DRILLING CO.  
 COMMENCED 5-29-63  
 COMPLETED 6- 5-63  
 INITIAL PRODUCTION B & A

LOCATION: NE NE NW  
 SECTION 34-22S-10W  
 RENO COUNTY, KANSAS

CASING RECORD:  
 8 5/8" @213' W/220 SACKS

<u>FORMATION</u>	<u>DEPTH</u>
SURFACE HOLE	213
SHALE	401
ANHYDRITE	408
SHALE	825
SHALE AND LIME	1485
LIME AND SHALE	2040
SHALE AND LIME	2375
LIME AND SHALE	2730
LIME	2895
LIME AND SHALE	3020
SHALE AND LIME	3180
LIME	3425
LIME AND SHALE	3523
CONGLOMERATE	3583
CHERT	3615
SHALE AND SAND	3687
LIME	TD 3720

10-22-63  
**RECEIVED**  
 STATE CORPORATION COMMISSION

OCT 22 1963

CONSERVATION DIVISION  
 Wichita, Kansas

I HEREBY CERTIFY THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REX &amp; MORRIS DRILLING COMPANY

BY Paul D. Koonz  
 PAUL D. KOONZ, GEOLOGIST

STATE OF KANSAS )  
 ) ss.  
 COUNTY OF BUTLER)

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC, THIS 16TH DAY OF JUNE, 1963

Mary Bailey  
 MARY BAILEY-NOTARY PUBLIC

MY COMMISSION EXPIRES: 28 JULY 1963