

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Reno County. Sec. 26 Twp. 22 Rge. 10 (E) W (W)  
Location as "NE/CNW&SW&" or footage from lines C SE NE  
Lease Owner Lee Phillips Oil Company  
Lease Name Fair "C" Well No. 1  
Office Address 1407 Union National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed April 10, 19 60  
Application for plugging filed " 10, 19 60  
Application for plugging approved " 10, 19 60  
Plugging commenced " 10, 19 60  
Plugging completed " 10, 19 60  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3727 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	317'	8 5/8"	317	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used  
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Filled hole with heavy mud from total depth to 300' with plug and 15 sacks  
of cement at that point. Mud to 35' with plug and 10 sacks of cement at that  
point.

4-19-60

RECEIVED  
ST. CORPORATION COMMISSION

APR 19 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Company  
Address P. O. Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Allan Harms (employee of owner) or (owner or operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms  
P. O. Box 184, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of April, 19 60

My commission expires January 20, 1960

Mary E. Van Pelt  
Notary Public.



DRILLERS LOG

Company: Lee Phillips Oil Company  
 Farm: Fair "C" #1  
 Commenced: March 30, 1960  
 Elevation: 1747 KB

C SE NE Section 26-22-10W  
 Reno County, Kansas  
 Completed: April 10, 1960

0 - 70	sand
70 - 150	sand & shale
150 - 200	sand
200 - 390	red bed
390 - 410	anhydrite
410 - 925	red bed & shale
925 - 1175	shale & lime
1175 - 2050	lime & shale
2050 - 2700	shale & lime
2700 - 2994	lime
2994 - 2999	shale
2999 - 3022	lime
3022 - 3175	shale
3175 - 3467	lime
3467 - 3525	lime & shale
3525 - 3585	lime, shale, & chert
3585 - 3647	lime & shale
3647 - 3692	lime & chert
3692 - 3702	shale
3702 - 3727	coring
3727	total depth

Set 317 feet of 8 5/8" surface pipe. Cemented with 300 sacks of cement with 2% calcium chloride. 750 flow seal.

Top: Anhydrite - 390'  
 Heabner - 2994'  
 Dr. Lime - 3141'  
 Lansing KC - 3170'  
 Kinderhook - 3529'  
 Viola - 3584'

See electric log.

Dry, plugged and abandoned.

4-19-60  
**RECEIVED**  
 STATE CORPORATION COMMISSION

APR 19 1960

CONSERVATION DIVISION  
 Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS )  
 ) ss.  
 COUNTY OF BARTON)

I, Allen Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Subscribed and sworn to before me this 15 day of April, 1960.

My commission expires January 20, 1962.

Mary E. Van Belt  
 Notary Public