

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County. Sec. 28 Twp. 22 Rge. (E) 10 (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW/4

Lease Owner M. B. Armer

Lease Name Parrett Well No. 1

Office Address 710 Petroleum Bldg., Wichita, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well - Depleted

Date well completed March 12, 19 54

Application for plugging filed April 6, 19 55

Application for plugging approved April 7, 19 55


Plugging commenced April 7, 19 55

Plugging completed April 9, 19 55

Reason for abandonment of well or producing formation Well depleted

If a producing well is abandoned, date of last production Feb. 17, 19 55

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Ruel Durkes

Producing formation Viola Depth to top 3557 Bottom Total Depth of Well 3672 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	203	None
				5 1/2"	3656	3046

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with sand to 3550 ft., dumped 6 sax cement at 3550 ft. with dump bailer. Top of cement 3507'. Filled hole with mud to 200', set rock bridge, dumped 15 sax cement. Top of cement 155 ft. Filled with mud to 25 ft., set rock bridge, dumped 5 sax cement for cap.

4-28-55

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co.

Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Handwritten Signature]

(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of April, 19 55

My commission expires February 13, 1956. [Signature] Notary Public.

PLUGGING
WV SEC 28 T22 R10W
COOK PAGE 109 LINE 31

15-155-00351-0000


KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **M. B. Armer**
FARM **Parrett** NO. **1**

SEC. **28** T. **22S** R. **10W**
LOC. **NE NW NW**

TOTAL DEPTH **3672**
COMM. **2/25/54** COMP. **3/11/54**
SHOT OR TREATED
CONTRACTOR **Armer, Inc.**
ISSUED

COUNTY **Reno**
KANSAS



CASING
20 10
15 8 **203.07'**
12 6
13 5 **3656'**

ELEVATION **1780 K.B.**
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand 150
Shale 210
Red Bed & Sand 295
Shale & Shells 430
Anhydrite 445
Shale & Shells 975
Shale, Shells & Salt, & Red Bed 1350
Lime & Shale 1850
Shale & Shells 2030
Shale & Lime 2150
Shale & Shells 2465
Shale 2640
Sandy Shale & Lime 2770
Lime & Shale 2965
Lime 3015
Lime & Shale 3225
Lime 3505
Shale & Cherty Lime 3567
Lime & Chert 3569
Chert 3579
Cherty Lime & Shale 3606
Shale & Lime 3655
Lime 3672

FORMATION TOPS (R.B. Meas.)

TOPEKA 2729
BROWN LIME 3164
LANS.K.C. 3190
VIOLA 3562
SIMPSON 3601
ARBUCKLE 3660
R.T.D. 3677

TOPS CORRECTED 5' UP HOLE BY STEEL LINE MEASURE

TOPEKA 2724
BROWN LIME 3159
LANS.K.C. 3185
VIOLA 3557
SIMPSON 3596
ARBUCKLE 3655
R.T.D. 3672

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports:

4-28-55

ARMER, INC.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1955

By *[Signature]*

STATE OF KANSAS CONSERVATION DIVISION
SS: Wichita, Kansas
COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 15th day of March, 1954.

[Signature]
Notary Public

My Commission expires February 13, 1956.

PLUGGING
FILE SEC 28 T 22 R 10W
BOOK PAGE 109 LINE 21