


15-155-02048-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Reno County, Sec. 28 Twp. 22 Rge. (E) 10 (W)
Location as "NE/CNW/SW" or footage from lines SW NW NW/4
Lease Owner Armer Drilling Company
Lease Name Parrett Well No. 2
Office Address 710 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed March 23, 19 54
Application for plugging filed March 23, 19 54
Application for plugging approved March 23, 19 54
Plugging commenced March 23, 19 54
Plugging completed March 23, 19 54
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Durkee
Producing formation Depth to top Bottom Total Depth of Well 3625 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	294'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Gunned the Pits up, circulated for 30 minutes
with drill pipe half way out of hole. Set Bridge at
250 ft. with 20 sacks cement through 8 jts. of drill
pipe. Set plug at 40 ft. and 10 sacks cement at the
surface.

RECEIVED
STATE CORPORATION COMMISSION
APR 7 1954
CONSERVATION DIVISION
Wichita, Kansas

4-7-54

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Armer, Inc.
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1954

My commission expires February 13, 1956. Notary Public.


PLUGGING
FILE REC 28 T 22 R 10W
BOOK PAGE 22 LINE 37

KANSAS GEOLOGICAL SOCIETY 15-155-02048-0000
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **H. B. Arner**
 FARM **Farrett** NO. **2**

SEC. **28** T. **22** R. **10W**
 LOC. **SH NW SW**

TOTAL DEPTH **3625'**
 COMM. **3/12/54** COMP. **3/23/54**
 SHOT OR TREATED
 CONTRACTOR **Arner, Inc.**
 ISSUED

COUNTY **Sedgwick**
 KANSAS


CASING
 20 10
 15 8 **29 1/2'**
 12 6
 13 5

ELEVATION **1777 X.B.**
 PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	150
Red Bed & Shells	120
Anhydrite	450
Red Bed, Shale & Shells	
& Salt	1005
Shells & Shale	1370
Shale, Shells & Sandy	
lime	1530
lime & shale	2765
Broken lime	2865
lime	3000
Shale & lime	3215
lime	3440
lime & shale	3520
lime, shale & chert	3569
lime & chert	3580
chert & shale	3600
chert, shale & sand	3625

FORMATION TOPS (X.B. Feet.)

EROLS LINE	3162
LAUREL	3199
VIOLA	3559
SIMPSON	3592

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARNER, INC.

By *L. P. Spruill*
RECEIVED
 STATE CORPORATION COMMISSION
 APR 7 1954
 4-7-54

STATE OF KANSAS
 COUNTY OF SEDGWICK

CONSERVATION DIVISION
 Wichita, Kansas

Subscribed and sworn to before me, a notary public, in and for said County and State this 26th day of March, 1954.

Robert Lacey
 Notary Public

My Commission expires February 13, 1956.

PLUGGING
 FILE SEC 28 T 22 R 10W
 BOOK PAGE 12 LINE 37