


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Reno County. Sec. 15 Twp. 23 Rge. 4 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NE NW SE

Lease Owner T G T PETROLEUM CORP.
Lease Name NELSON Well No. "A" 1
Office Address 209 E. William Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry



Locate well correctly on above
Section Plat

Date Well completed 11-3 19 78
Application for plugging filed 11-3 19 78
Application for plugging approved 11-3 19 78
Plugging commenced 10:30 A.M. 11-3 19 78
Plugging completed 11:00 A.M. 11-3- 19 78
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3440
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Hole full of heavy mud to 690'
Pumped 25 sx. common cement thru drill pipe @ 690
2 sx in rathole
plugged water well 1 sack

11-7-78

RECEIVED
STATE CORPORATION COMMISSION

NOV 7 1978

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor _____ CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton
Larry Curtis (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Larry Curtis

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1978

Bessie M. DeWerff
Bessie M. DeWerff Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

T G T PETROLEUM CORP. - OPERATOR

NELSON "A" 1
NE NW SW 15-23-4
RENO COUNTY, KANSAS

T. D. 3440
ELEV. 1446 KB

COMMENCED: 10-27-78
COMPLETED: 11-3-78

Casing

10-3/4" set at 215'
8-5/8" set at 707'

Cement

W/275 sx Common cement, 2% Gel, 3% CC
W/100 sx 60/40 Pozmix, 2 % Gel, 3% CC

FORMATION

Sand & Shale
Shale
Shale & Limestone
Shale
Shale W/lime
Lime W/Shale
Shale & Lime
Lime
Shale
Lime

DEPTH

0 - 215
215 -430
430 -787
787 -1068
1068-1408
1408-2403
2403-2573
2573-3047
3047-3327
3327-3440

TOPS

Tarkio 1719
Brn. Lime 2573
Lansing 2592
K C 2825
Husk pucking 2995
B K/C 3017
Chke Shale 3181
Cherty Cong. 3313
Miss. 3327
Osage 3384
R.T.D. 3440

AFFIDAVIT

State of KANSAS County of BARTON

I, Larry Curtis of the L. D. Drilling Company

being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Larry Curtis
Larry Curtis

Subscribed and sworn to before me on this 6th Day of November 1978

My commission expires: 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

Bessie M. DeWerff
Notary Public, Bessie M. DeWerff
STATE CORPORATION COMMISSION

NOV - 7 1978
11-7-78
CONSERVATION DIVISION
Wichita, Kansas