

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

KINGMAN

County, Sec. 7 Twp. 27S Rge. (E) 6 (W)

Location as "NE/CNW&SW" or footage from lines cse se

Lease Owner Shawver Armour, Inc.

Lease Name Hampel Well No. 1

Office Address 817 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Dec. 7 19 66

Application for plugging filed Dec. 7 19 66

Application for plugging approved Dec. 7 19 66

Plugging commenced Dec. 7 19 66

Plugging completed Dec. 7 19 66

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie V Elving, Plugger

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3460 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand		0	10			
Clay		10	20			
Red Bed		20	300	8 5/8	245	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'
#1 Plug - 3/4 sk Hulls - Howco Plug 25 sk
Heavy mud to 40'
1/4 sk Hulls, Howco Plug 8 sk cmt
Bridge rat hole @ 7' and 2 sk cem.

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shawver Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
James M. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour
James M Armour
817 Central Building
(Address)

SUBSCRIBED AND SWORN to before me this 13 day of December, 19 66

My commission expires Dec. 29, 1967
Marjorie Hall Notary Public.

DRILLER'S LOG

FARM NAME: HAMPEL #1 LOCATION: CSE SE
 Sec. 7-27S-6W
 CONTRACTOR: Shawver Armour, Inc. Kingman County, Ks.
 OWNER: Shawver Armour, Inc. ELEVATION: 1484 K.B.
 COMMENCED: November 29, 1966 COMPLETED: December 7, 1966
 CASING RECORD: Set 245' 8 5/8" w/ 230 sx cem., 5 sx c.c.

FORMATION:

Sand 10
 Clay 20
 Red Bed 300
 Shale 815
 Lime & Shale 1120
 Shale & Lime 1220
 Lime 1340
 Lime & Shale 2255
 Shale & Lime 2547
 Lime 2677
 Lime & Shale 2987
 Lime 3460 RTD
 D & A

TOPS:

Heebner 2794
 Brown Lime 3030
 Lansing 3045
 Hertha 3438

RECEIVED 12-15-66
 STATE CORPORATION COMMISSION
 DEC 15 1966
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 SEDGWICK COUNTY)

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour
 James M. Armour, President

Subscribed and sworn to before me this 13th day of December 1966.

My commission expires December 29, 1967

Marjorie Hall
 Marjorie Hall, Notary Public