


15-095-00365-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Kingman County. Sec. 7 Twp. 27S Rge. 6W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Osage Oil & Gas / Sierra Petroleum Co - Contr.
Lease Name FRAKES Well No. 1
Office Address Petroleum Bldg., Wichita, Ks/ 208 Petroleum Bldg., Wichita
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 1/10/59 19
Application for plugging filed 1/9/59 19
Application for plugging approved 1/9/59 19
Plugging commenced 1/10/59 19
Plugging completed 1/10/59 19
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampl, Pretty Prairie, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	225	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 4200 up to 210'. Build bridge, hulls, wood plug with 20 sacks cement through drill pipe. Fill hole with mud up to 40'. Bridge with hulls wood plug, 10 sks cement to cellar 0.
Job completed 1 a.m. 1/10/59

1-13-59

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address Box 232, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 59

Margie Cooper

Notary Public.

My commission expires 1-30-61.

PLUGGING
FILE SEC 7 T 27 R 6W
BOOK PAGE 10 LINE 30

Osage Oil & Gas Co - Owner

Sierra Petroleum Co - Contr.

FRAKES #1

NE NE NW Sec. 7-27S-6W
Kingman County, Kansas

Total Depth: 4200'

Elev: 1502' KB

Comm: 12/26/58

Comp: 1/10/59

Casings:

Cements:

8 5/8 @ 225'

with 165 sacks cement

FORMATION	DEPTH
Sand & Red bed	75
Red Bed	215
Anhydrite	225
Red Bed, Shale & Gyp	430
Shale & Gyp	700
Shale & Shells & salt	925
Lime & Shale	1115
Gyp & Shale	1225
Lime & shale	1795
Shale & shells	2080
Shale & lime	3205
Lime	3557
Lime & shale	3745
Lime	3810
Chert & Lime	3885
Mississippi Lime	3965
Cherty lime	3988
Lime	4035
Lime & shale	4153
Lime	4161
Chert, lime & shale	4200

Tops: Anhydrite	KANSAS	215
Conglomerate		3784
Mississippi		3792
Kinderhook		4024
Misner		4140
Viola		4156
Simpson		4165

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Hender

Subscribed and sworn to before me this 12th day of January, 1959.

Margie Cooper
Notary Public

My commission expires: 1-30-61.

PLUGGING
FILE SEC 7 127 R6W
BOOK PAGE 10 LINE 30

1-13-59
RECEIVED
STATE COMMISSION
JAN 13 1959
COMMISSION DIVISION