

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - ✓ (of this well)

Operator's Full Name K&E Drilling Inc,

Complete Address 816 Union Center, Wichita, Ks. 67202

Lease Name John Brown Well No. 1

Location NW NE SE Sec. 35 Twp. 26S Rge. 13 (E) (W) X

County Pratt Total Depth 4354

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 10:45 Am. Day 30 Month 7 Year 1980

The above well was plugged as follows:

479' 8 5/8" casing W/300 sax cement. 5 1/2" casing set at 4352' W/150
sax cement. Plug back to 3933'-Pref's at 3772'-3778'-Sand back to
3750'-Top sand W/5 sax mixed cement W/dump bailer-Pull 3610' casing
Sun mixed & pumped 8 sax hulls-25 sax gel-150 sax 50/50 posmix cmt.
W/4% gel & 3% cc to top of casing. Shut in W/300# pressure.

RECEIVED
STATE CORPORATION COMMISSION
AUG - 1 1980 8-1-80
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8-1-80

INV. NO. 2746-W