

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - ✓ (of this well)

Operator's Full Name K. & E Drilling Inc.

Complete Address 816 Union Ctr., Wichita, Ks. 67202

Lease Name John Brown Well No. 2

Location SE NW SE Sec 35 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4380

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 1:30 Pm. Day 30 Month 7 Year 1980

The above well was plugged as follows:

458' 8 5/8" casing w/325 sax cement. 5 1/2" casing set & 4377' w/150 sax
cement-Plug back to 4287'-Preforated at 3899' To 3901'-Sand back to
3850'-Top sand w/5 sax mixed cement w/dump bailer-Pull 2715' casing-
Sun mixed & pumped 8 sax hulls-25 sax gel-150 sax 50/50 posmix cement
w/4% gel & 3% cc to top of casing. Shut in w/200# pressure.

RECEIVED 8-1-80
STATE CORPORATION COMMISSION
AUG - 1 1980
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8-1-80

INV. NO. 2747-W