

1 050445

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,546 - 80-00

SE NE NW, SEC. 34, T 26 S, R 13 W/E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5692

Lease Name Sueken Well # 2

Operator: American Petrofina Company of Tex Co. County Pratt 145.44

Name & Address 1601 NW Expressway, Suite 900

Well Total Depth 4475 feet

Oklahoma City, OK 73118

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 469 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 8:00 pm Day: 1 Month: February Year: 19 85

Plugging proposal received from Butch Steinert

(company name) Eagle (phone) 316-682-5513

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 840' with 50 sx cement

2nd plug at 510' with 40 sx cement

solid bridge

3rd plug hulls + plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 10:00 pm Day: 1 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 840' with 50 sx cement, 2nd plug at 510' with 40

sx cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 07 1985

2-7-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) did not observe this plugging.

DATE 2-13-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 6947

2-1