

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

3-2-66

RECEIVED  
STATE CORPORATION COMMISSION

MAR 2 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Champlin Petroleum Company

Complete Address: P. O. Box 308, Ellinwood, Kansas

Lease Name Moore "C" Well No. # 3

Location NE NE SW Sec. 11 Twp. 26 Rge. 14 (E) (W) W

County Pratt Total Depth 3970'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 6:40AM Day 28th Month Feb. Year 1966

The Above well was plugged as follows:

252' of 8 5/8" surface pipe, cement circulated with 225 sacks. 1st  
cementing plug and 1/4 sack of hulls was pushed in fluid to 240', and  
cemented with 25 sacks, through the drill pipe at 240'. Hole was filled  
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls  
on fluid at 40', and cemented with 10 sacks to the base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 3/2/66

INV. NO. 2809-w