

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1964
8-10-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Time Petroleum Company

Complete Address: 815 Union National Bldg., Wichita, Kansas

Lease Name Moore Well No. # 1

Location NW SE SE Sec. 3 Twp. 26 Rge. 14 (E) (W) W

County Pratt Total Depth 4318

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Strata Drilling Inc.

Address: 2421 Tenth St., Great Bend, Kansas License No.

Operation Completed: Hour 1:30PM Day 9th Month August Year 1964

The Above well was plugged as follows:

290' of 8 5/8" surface pipe, cement circulated. Fluid level was up in
the hole. 1st cementing plug and 1/2 sack hulls was pushed in fluid to
275', and cemented with 25 sacks, through the drill pipe. Hole was fill-
ed with drilling mud to 40', 2nd cementing plug, bridged solid with hulls,
and cemented with 10 sacks to the base of the cellar. Rat and mouse hole
bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/10/64

INV. NO. 9629-W

Signed: Archie Elving
Well Plugging Supervisor