

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1974

7-1-74

Form CP 1

STATE OF KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

File All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217

Locate well correctly on above
Section Plat

Pratt County, Sec. 10, Twp. 26, Rge. 14 (E) (W)
 Location as "NE/SW" or footage from lines SE NE SE
 Lease Owner Raymond Oil Co., Inc.
 Lessee Name Moore D#1 Well No.
 Office Address Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed 19
 Application for plugging filed 19
 Application for plugging approved 19
 Plugging commenced 6/20/74 19
 Plugging completed 6/24/74 19
 Reason for abandonment of well or producing formation depleted.
 If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
 Producing formation Depth to top Bottom Total Depth of Well 4448 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9"	907'	none
				5 1/2"	4446'	1918'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 4400' and dumped 5 sacks cement.
 Shot pipe at 1900', pulled 58 joints. Set 10' rock bridge at 250' and dumped 4 yards ready mix.

PLUGGING COMPLETE

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet)
 Address KNIGHT CASING PULLING CO., INC.
 CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
 NOEL J. KNIGHT ss. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
 CHASE, KANSAS (Address)

Subscribed and sworn to before me this 25th day of June 1974

MARGARET MELCHER
 NOTARY PUBLIC
 Rice County, Kansas
 My Commission Expires
 Feb. 15, 1975

Margaret Melcher
 Notary Public.

15-151-10902-0000
COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company CHAMPLIN REFINING CO.
Farm Marvin G. Moore No. 1
"D"

SEC. 10 T. 26 R. 14W
SE-NE SE
1650' fr SL, 330' fr EL SE/4

Total Depth. 4448
Comm. 9-18-53 Comp. 10-12-53
Shot or Treated.
Contractor.
Issued. 1-2-54

County Pratt

KANSAS



Elevation. 1990 DF

Production. 170 BO, 30 BW

CASING:
9 in. 906.87' w/ 500 sx cmt.
5 1/2 4446.49' w/ 175 sx cmt.
2 in. 4240'

Figures indicate Bottom of Formations.

sand	130
sand, gravel & red bed	310
sand & red bed	550
sand, red bed & shells	900
shale, red bed & shells	1520
shale & shells	1605
shale & anhydrite	1695
shale & shells	1760
shale & lime	3947
shale, lime & chert	3975
shale & lime	4195
shale & cherty lime	4227
conglomerate	4237
shale, lime & chert	4278
shale	4281
shale & lime	4315
lime & chert	4365
cherty lime	4382
lime & chert	4406
lime & sand	4426
shale, lime & sand	4445
shale & lime	4448
Total Depth	

TOPS:	
Heebner	3638
Lansing K C	3822
Base K C	4070
Top Sooy Conglomerate	4204
Kinderhook	4260
Viola	4315
Simpson	4413

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1974
CONSERVATION DIVISION
Wichita, Kansas

6-5-74