


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pratt

County. Sec. 10 Twp. 26 Rge.      (E) 14 (W)

Location as "NE/CNWxSWx" or footage from lines NE NW NW

Lease Owner Icer Addis

Lease Name Moore Well No. 1

Office Address Post Office Box 519, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-19-60 19

Application for plugging filed 9-19-60 19

Application for plugging approved 9-19-60 19

Plugging commenced 9-19-60 19

Plugging completed 9-19-60 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production      19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Stafford, Kansas

Producing formation      Depth to top      Bottom      Total Depth of Well 3845 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	376'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

1/3 sack of hulls, wooden plug set at 350 ft.  
Mixed 20 sacks cement through drill pipe.

1/3 sack of hulls, wooden plug set at 35 ft.  
Mixed 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 22 1960

CONSERVATION DIVISION  
WICHITA, KANSAS

9-22-60

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address Post Office Box 97, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton Contractor      ss.

V. Richard Hoover, President (employee of     ) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover

(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of September, 19 60

My commission expires May 19, 1960

Norris Taylor  
Norris Taylor

Notary Public.



WELL LOG

Icer Addis  
P.O. Box 519  
Great Bend, Kansas

#1 Moore  
NE NW NW Sec. 10-26-14W  
Pratt County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 9-12-60  
Completed: 9-19-60  
D & A

RECEIVED  
STATE CORPORATE COMMISSION  
SEP 22 1960  
CONSERVATION DIVISION  
Wichita, Kansas

Casing Record: 8 5/8" at 376' with 250 sacks Quickset Cement.

9-22-60

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & Clay	0	240'	1990' Gr.
Redbed	240'	360'	1992' D.F.
Shells & Clay	360'	370'	1995' K.B.
Redbed	370'	700'	
Sand	700'	880'	
Sand & Shale	880'	915'	
Anhydrite	915'	930'	
Shale & Shells	930'	1880'	
Shale & Lime	1880'	2050'	
Lime & Shale	2050'	2190'	
Lime	2190'	2580'	
Lime & Shale	2580'	3400'	
Lime	3400'	3625'	
Shale & Lime	3625'	3790'	
Lime	3790'	3845'	
Total Depth	3845'		

<u>FORMATION TOPS</u>	
Anhydrite	915' (+1080)
Heebner	3625' (-1630)
Brn Lime	3786' (-1791)
Lansing	3815' (-1820)

<u>DST #1</u>	
Depth	3817 - 45'
Tool Open	1 Hour
Recovery:	240' Muddy Water
IBHP =	1360#/20'
IFP =	80# FFP = 128#
FBHP =	1196#/30"
D & A	

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE NW NW Sec. 10-26-14W, Pawnee County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO. INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 19th day of September, 1960.

My Commission expires 5/19/62

*Norris Taylor*  
Norris Taylor, Notary Public