

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 10 TWP. 26S RGE. 14 W  
Location as in quarters or footage from lines:

NW NW SE

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Lease Owner White & Ellis Drilling, Inc.  
 Lease Name Moore Well No. #1  
 Office Address 401 E. Douglas - Suite 500 Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry  
 Date Well Completed 11-30-82  
 Application for plugging filed 11-30-82  
 Plugging commenced 11-30-82  
 Plugging completed 11-30-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4317'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size   | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 330'   | NONE       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 380', plug, Spot 50 sx. cement thru drillpipe.  
mud to 330', Plug, Spot 40 sx. cement thru drillpipe.  
Mud to 40', Spot 10 sx. cement thru drillpipe.  
10 sx. cement in rathole.  
5 sx. cement in water well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.  
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.


Ernest Sifford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford  
401 E. Douglas #500 Wichita,  
(Address) Ks. 67202


SUBSCRIBED AND SWORN TO before me this 10<sup>th</sup> day of December, 1982

Carolyn J. Tjaden  
Carolyn J. Tjaden - Notary Public  
STATE CORPORATION COMMISSION

My Commission expires:



12-13-82  
DEC 15 1982



15-151-21188-0000

# WHITE

AND ELLIS DRILLING, Inc.

## DRILLERS LOG

OPERATOR: White & Ellis Drilling, Inc. 401 E. Douglas-Suite 500 Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Moore Well No. #1

Sec. 10 T. 26S R. 14W Spot NW NW SE

County Pratt State Kansas Elevation \_\_\_\_\_

### Casing Record:

Surface: 8 5/8" @ 330' with 300 sx.

Production: @ with \_\_\_\_\_ sx.

Type Well: D & A Total Depth 4317'

Drilling Commenced 11-19-82 Drilling Completed 11-30-82

| Formation   | From | To   | Tops        |      |
|-------------|------|------|-------------|------|
| Cellar      | 0    | 7    | Anhydrite   | 1880 |
| Shale, Lime | 7    | 1011 | Lansing     | 3799 |
| Sand        | 1011 | 1356 | Kansas City | 4020 |
| Shale, Lime | 1356 | 2032 | Mississippi | 4205 |
| Sand, Shale | 2032 | 2727 | Kinderhook  | 4288 |
| Lime, Shale | 2727 | 3120 |             |      |
| Shale, Lime | 3120 | 3262 |             |      |
| Lime, Shale | 3262 | 3524 |             |      |
| Shale, Sand | 3524 | 3660 |             |      |
| Shale, Lime | 3660 | 3799 |             |      |
| Lime        | 3799 | 3912 |             |      |
| Lime, Shale | 3912 | 4020 |             |      |
| Lime        | 4020 | 4288 |             |      |
| Shale       | 4288 | 4317 |             |      |

RECEIVED  
STATE GEOLOGICAL COMMISSION

DEC 13 1982

12-13-82

CONSERVATION DIVISION  
Wichita Kansas