

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP 1


Give All Information Completely  
Make Accurate Maps of  
Mines or Belong Report to  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD

Pratt County, Sec. 14 Twp. 26 Rge. 14 (E) (W)

Location as "NE/CNWSW2" or footage from lines NW NW NW  
Lease Owner Raymond Oil Co., Inc.  
Lessee Name Mary Moore #1 Well No. \_\_\_\_\_  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6/14/74 19\_\_\_\_  
Plugging completed 6/19/74 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4370 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	919	none
				5 1/2"	4102	2851'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked bottom, ran sand to 4080' and dumped 5 sacks cement.  
Loaded hole, shot pipe at 3015', 2913', pulled 86 joints.  
Bailed hole to 250' and set 10' rock bridge, dumped 4 yards ready mix.

PLUGGING COMPLETE.

RECEIVED 6-25-74  
STATE CORPORATION COMMISSION  
JUN 25 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE  
NOEL J. KNIGHT ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
CHASE, KANSAS

SUBSCRIBED AND SWORN to before me this 20th day of June 1974

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

[Signature]  
Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas.

15-151-10014-0000  
COPY

Company—CHAMPLIN REFINING COMPANY  
Farm— Mary Moore . No. 1

SEC. 14 T. 26 R. 14W  
NW NW NW  
330' fr WL  
330' fr NL NW  
County—Pratt  
KANSAS

Total Depth. 4370  
Comm. 11-11-63 Comp. 11-25-53  
Shot or Treated.  
Contractor.  
Issued. 1-23-54



CASING:  
8 5/8" 918.91' com. w/525 sx  
8 1/2" 4402.37' com. w/150 sx  
2 1/2" 4340.14'

Elevation. 1985'  
Production: 94 BO & NW

Figures indicate Bottom of Formations.

sand 235  
red bed, gyp shells 595  
red bed, anhydrite 912  
anhydrite 925  
red bed & shale 1100  
shale, shells, salt 1690  
shale 1935  
limo 2095  
shale & limo 3848  
limo 3896  
shale & limo 3943  
limo 3984  
shale & limo 4218  
limo, conglomerate 4256  
conglomerate 4292  
conglomerate, sand 4294  
sand cored 4306  
shale & lim 4340  
shale, limo, chert 4370  
Total Depth

TOPS:  
Hoebner 3642  
Brown Lino 3795  
Lansing Kansas City 3825  
Conglomerate 4250  
Kinderhook Sand 4305  
Viola 4347

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1974  
CONSERVATION DIVISION  
Wichita, Kansas

6-5-74