

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 15 TWP. 26S RGE. 14W E/W  
Location as in quarters or footage from lines:  
SW SW NW


Lease Owner John J. Darrah, Jr.  
Lease Name Fowler-Moore #1 Well No. \_\_\_\_\_  
Office Address Century Plaza Bldg. Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 11-3-81  
Plugging completed 12-9-81  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Pratt.

\_\_\_\_\_ Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	920'	none
				4-1/2"	4435'	497'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 4250' and set 5 sacks cement. Picked up on pipe  
and it parted @497'. Pulled 12 joints. Squeezed hole with 25 sacks gel, 6 sacks hulls,  
displaced with 200 sacks 50/50 pos, 4% gel, 3% cc. Plugging Completed.


12-14-81  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 24 1981

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 81



Irene Hoover  
Notary Public.

My Commission expires: \_\_\_\_\_

DRILLERS LOG

COMPANY: Armstrong & Jackman  
 CONTRACTOR: Aspen Drilling Co.  
 LEASE NAME: Towler #1  
 LOCATION: SW SW NW Sec. 15-T26S-R14W  
 Pratt County, Kansas  
 ELEVATION: 1994 KB  
 SURFACE CASING: 23 jts. (928') 8 5/8"  
 COMMENCED: December 3, 1969  
 COMPLETED: December 15, 1969  
 ROTARY TOTAL DEPTH: 4455'

<u>FORMATION</u>	<u>DEPTH</u>	
Shale & Sand	225	Ran 23 jts. (928') 8 5/8" casing set
Shale	635	at 920' w. 275 sacks Pozmix and 250
Shale & Red Bed	909	sacks Sunset.
Anhydrite	934	
Shale & Shells	1835	DST #1, 3984-4000
Shale & Lime	1955	DST #2, 4270-4297
Lime & Shale	2810	DST #3, 4290-4327
Shale & Lime	3040	DST #4, 4381-4455
Shale & Shells	3270	
Shale & Lime	3570	Ran electric log
Lime & Shale	3900	
Lime	4000	D & A
Lime & Shale	4273	
Mississippi	4325	
Kinderhook	4327	
Kinderhook Shale	4395	
Shale & Lime	4435	
Viola	4455	
RTD	4455	

1-7-70

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 7 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

RECEIVED

STATE CORPORATION COMMISSION  
 AFFIDAVIT STATE CORPORATION COMMISSION  
 AUG 31 1981

State of Kansas )  
 ) ss:  
 County of Barton )

CONSERVATION DIVISION  
 Wichita, Kansas

AUG 30 1981

CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

Theora Scott  
 Theora Scott, AFFIANT

Subscribed and sworn to before me this 2nd day of January, 1970.



My commission expires: June 17, 1972

Dorothy King  
 Dorothy King, Notary Public